

# ALLEGAN COUNTY ROAD COMMISSION


## 46TH STREET CULVERT REPLACEMENT PROJECT 170' SOUTH OF 143RD AVENUE OVERISEL TOWNSHIP

EXCEPT WHERE OTHERWISE INDICATED ON THESE PLANS OR IN THE PROPOSAL AND SUPPLEMENTAL SPECIFICATIONS CONTAINED THEREIN, ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 MICHIGAN DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION.


THE PLACING OF PAVEMENT MARKINGS AND TRAFFIC CONTROL SIGNS SHALL BE DONE IN ACCORDANCE WITH THE 2011 MICHIGAN MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AS AMENDED.

THE IMPROVEMENTS COVERED BY THESE PLANS ARE IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2011 EDITION, A POLICY ON GEOMETRIC DESIGN OF HIGHWAYS AND STREETS.

THE CONTRACTOR SHALL DIAL MISS DIG @ 811 FOR PROTECTION OF UNDER GROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174 OF 2013 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.



UTILITY CONTACTS	
<b>ELECTRIC</b> CONSUMERS ENERGY 4000 CLAY AVE, SW GRAND RAPIDS, MI 49548 616-530-4185 MS. KYLEE MAYCROFT grvimp@cseenergy.com	<b>GAS</b> SEMCO 739 PAW PAW DRIVE HOLLAND, MI 49422 800-476-1441 EXT. 5788 MR. GREG STROH greg.stroh@semcoenergy.com
<b>TELEPHONE</b> FRONTIER 601 N. US 131 THREE RIVERS, MI 49093 269-273-0383 MR. JEREMY MCCORD jeremy.mccord@fr.com	"MISS DIG" 811
<b>CABLE</b> CHARTER 4176 COMMERCIAL AVE PORTAGE, MI 49002 269-217-8152 MR. LEO SCOFIELD leo.scotfield@charter.com	
<b>GAS</b> CONSUMERS ENERGY 2500 E CORK ST KALAMAZOO, MI 49001 269-337-2366 MR. KYLE OAK kyle.oak@cseenergy.com	



- INDEX OF PLANS**
- 1 - COVER SHEET
  - 2 - TYPICAL SECTIONS, DETAILS, & NOTES
  - 3 - PLAN & PROFILE AND SOIL EROSION & SEDIMENTATION CONTROL PLAN
  - 4 - DETOUR ROUTES

ALLEGAN COUNTY, MICHIGAN  
NOT TO SCALE

**CONTRACT FOR ROAD IMPROVEMENTS**  
CULVERT REPLACEMENT INCLUDING GRADE ESTABLISHMENT, SAND SUBBASE, AGGREGATE BASE, HMA PAVING (0.28 MILES), GRAVEL SHOULDERS, PAVEMENT MARKINGS, AND RESTORATION ON 46TH STREET APPROXIMATELY 170 FEET SOUTH OF 143RD AVENUE IN OVERISEL TOWNSHIP, ALLEGAN COUNTY.

PREPARED UNDER THE SUPERVISION OF:


RYAN P. BROWN  
REGISTERED PROFESSIONAL ENGINEER No. 65933

**Board of County Road Commissioners  
Of Allegan County**  
1308 LINCOLN ROAD  
ALLEGAN, MICHIGAN 49010-9762  
www.alleganroads.org  
TELEPHONE (269) 673-2184 FAX (269) 673-5922

REVISIONS						
1	2	3	4	5	6	7

**46TH STREET CULVERT REPLACEMENT**  
OVERISEL TOWNSHIP - 170' SOUTH OF 143RD AVENUE  
COVER SHEET

DRAWN BY:	RPB
REVIEWED BY:	JSE
DATE:	JANUARY 2019
SCALE:	NONE



TYPICAL SECTION - 46TH STREET


SCALE: 1" = 5'

TYPICAL FILL SECTION  
 APPLY TOPSOIL SURFACE, SALV. LM (3 INCHES); SEEDING, MIXTURE TUF (220#/ACRE); FERTILIZER, CHEMICAL NUTRIENT, CL A (176#/ACRE); MULCH (2 TONS/ACRE); AND MULCH ANCHORING TO ALL DISTURBED AREAS (TYP.) INSTALL MULCH BLANKETS ON ALL FORESLOPES GREATER THAN 1 ON 3 OR AS DIRECTED BY THE ENGINEER IN THE FIELD.

STRIP TOPSOIL WITHIN 1 ON 1 INFLUENCE OF ROADWAY TO BE INCLUDED IN THE ITEM OF STATION GRADING (TYP.)

HMA, 13A MODIFIED (TOP)  
 HMA, 13A MODIFIED (LEVELING)  
 AGGREGATE BASE, 6 INCH  
 SUBBASE, CIP (12 INCHES)

TYPICAL DITCH IN CUT SECTION PROVIDE MULCH BLANKET, HIGH VELOCITY IN DITCH BOTTOM WHEN LONGITUDINAL GRADE IS GREATER THAN OR EQUAL TO 2.00% (TYP.).



TEMPORARY CHANNEL CROSS SECTION

SCALE 1" = 2'

ITEM	AWI	YIELD	PERFORMANCE GRADE
HMA, 13A MODIFIED (TOP)	260	220 #/SYD	P.G. 64 - 28
HMA, 13A MODIFIED (LEVELING)		220 #/SYD	P.G. 64 - 28
HMA BOND COAT (NOT A PAY ITEM)		0.05 TO 0.15 GAL/SYD	SS - 1h

HMA APPLICATION TABLE

PROJECT NOTES

THE "2012 STANDARD SPECIFICATIONS FOR CONSTRUCTION" AND "STANDARD PLANS" BY THE MICHIGAN DEPARTMENT OF TRANSPORTATION (MDOT) ARE HEREBY INCORPORATED INTO THESE CONTRACT DOCUMENTS. COPIES OF THESE STANDARDS ARE AVAILABLE FOR INSPECTION AT THE OFFICE OF THE ENGINEER.

THE CONTRACTOR WILL BE RESPONSIBLE FOR CONTACTING THE ALLEGAN COUNTY ROAD COMMISSION TO NOTIFY THEM THAT WORK IS COMMENCING AT LEAST ONE WEEK PRIOR TO CONSTRUCTION. THE ALLEGAN COUNTY ROAD COMMISSION WILL SET UP THE NECESSARY DETOUR ROUTE. THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING THE BARRICADES.

THE CONTRACTOR SHOULD NOTE THAT STATION GRADING WILL INCLUDE THE REMOVAL OF FENCES, CULVERTS, BRUSH, TREES SMALLER THAN 6", CONCRETE FOUNDATIONS, GUARDRAIL, AND MISCELLANEOUS ITEMS AS REQUIRED AND WILL ALSO INCLUDE ALL EARTH EXCAVATION, EMBANKMENT, AND ALL OTHER OPERATIONS NECESSARY TO DEVELOP THE DESIRED CROSS SECTION. ALL TOPSOIL AND OTHER UNSUITABLE MATERIAL LOCATED BENEATH THE PROPOSED PAVEMENT SECTION WILL BE REMOVED TO THE SUBGRADE ELEVATION AS PART OF STATION GRADING. ALL TOPSOIL REMOVED MAY BE STOCKPILED AND REUSED AS TOPSOIL SURFACE, SALV. LM.

ALL FILL FOR THIS PROJECT MUST BE OBTAINED AND FURNISHED BY THE CONTRACTOR. ALL REQUIRED FILL SHALL BE SELECTED EXCAVATED MATERIAL FROM THE SITE APPROVED BY THE ENGINEER, OR MDOT CLASS II GRANULAR MATERIAL FROM BORROW. EXCESS FILL WILL BE REMOVED FROM SITE BY THE CONTRACTOR. NO BORROW OR SOIL REMOVAL ARRANGEMENTS HAVE BEEN PREARRANGED FOR THIS PROJECT AND WILL BE THE TOTAL RESPONSIBILITY OF THE CONTRACTOR.

THE ITEM OF SUBBASE, CIP WILL BE PAID FOR AT PLAN QUANTITY EXCEPT IN THE CASE OF A DESIGN CHANGE OR DEMONSTRATED ERROR.

ALL DISTURBED AREAS NOT TO BE PAVED WILL BE RESTORED WITH TOPSOIL SURFACE, SALV. LM (3 INCHES), MDOT SEED MIXTURE TUF (220#/ACRE), FERTILIZER, CHEMICAL NUTRIENT, CL A (176#/ACRE); AND MULCH AND MULCH ANCHORING (2 TON/ACRE). TO BE PAID AS RESTORATION (LUMP SUM).

ADEQUATE DUST CONTROL MEASURES WILL BE MAINTAINED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER IN THE FIELD, TO BE INCLUDED IN THE VARIOUS ITEMS OF WORK.

THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING EXISTING DRAINAGE PATTERNS, AND WILL RESOLVE ANY DRAINAGE PROBLEMS ON ADJACENT PROPERTIES WHICH MAY RESULT FROM THE CONTRACTOR'S ACTIVITIES.


DATUM REFERS TO NAVD88 DATUM.

DIMENSIONS TAKE PRECEDENCE OVER SCALE. CONTRACTOR TO VERIFY ALL DIMENSIONS IN FIELD.

UTILITY NOTES


FOR PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 174 OF 2013, THE CONTRACTOR WILL CONTACT "MISS DIG" AT 811, A MINIMUM OF 72 HOURS, EXCLUDING SATURDAYS, SUNDAYS, AND HOLIDAYS, PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFYING UTILITY OWNERS WHO MAY NOT BE A PART OF THE "MISS DIG" ALERT SYSTEM.

THE CONTRACTOR WILL LOCATE ALL ACTIVE UNDERGROUND UTILITIES PRIOR TO STARTING WORK AND WILL CONDUCT HIS OPERATIONS IN A MANNER AS TO ENSURE THAT THOSE UTILITIES NOT REQUIRING RELOCATION WILL NOT BE DISTURBED.




SECTION A - A

SCALE 1" = 2'




SECTION B - B

SCALE 1" = 2'



TYPICAL JOINT SEAL DETAIL



TYPICAL INLET AND OUTLET SECTION

SCALE 1" = 2'

U/S ELEV. 680.00 LOW STEEL  
 D/S ELEV. 679.50


ELEV. - 673.99 WATER ELEVATION  
 JUNE 2018

U/S ELEV. 673.00 STREAM INVERT  
 D/S ELEV. 672.50

U/S ELEV. 672.00 CULVERT INVERT  
 D/S ELEV. 671.50

\* U/S ELEV. 671.00 TOP OF FOOTING  
 \* D/S ELEV. 670.50

\* U/S ELEV. 669.00 BOTTOM OF FOOTING  
 \* D/S ELEV. 668.50



FOOTING DETAIL


SCALE 1" = 1'

STEEL REINFORCEMENT SCHEDULE								
BAR	a	b	c	d	SIZE	LENGTH	NO. REQUIRED	TOTAL WEIGHT
EA101	21' - 6"				#6	21' - 6"	8	258
EK101	1' - 6"	1' - 0"	1' - 0"	1' - 6"	#6	6' - 6"	46	449

NOTES:  
 ALL RIGHT ANGLE BENDS IN REINFORCING STEEL TO BE MADE ABOUT A PIN OF THE MINIMAL DIAMETER ALLOWED BY THE STANDARD SPECIFICATIONS.

THE CONTRACTOR IS RESPONSIBLE FOR CHECKING THE ABOVE REINFORCING STEEL QUANTITIES AND LENGTHS PRIOR TO ORDERING DELIVERY OF STEEL.

STEEL REINFORCEMENT WITH BAR DESIGNATIONS BEGINNING WITH THE LETTER "E" WILL BE EPOXY COATED.



Board of County Road Commissioners  
 Of Allegan County  
 1308 LINCOLN ROAD  
 ALLEGAN, MICHIGAN 49010-9762  
 www.alleganroads.org FAX (269) 673-5922  
 TELEPHONE (269) 673-2184

REVISIONS						
NO.	DATE	DESCRIPTION	BY	CHKD	APP'D	SCALE
1						
2						
3						
4						
5						
6						
7						

46TH STREET CULVERT REPLACEMENT  
 OVERISEL TOWNSHIP - 170' SOUTH OF 143RD AVENUE  
 TYPICAL SECTIONS, DETAILS, & NOTES



DRAWN BY:  
 REVIEWED BY: RPB  
 DATE: JANUARY, 2019  
 SCALE: AS NOTED

LH 4954 2

REVISIONS	
1	
2	
3	
4	
5	
6	
7	

**46TH STREET CULVERT REPLACEMENT**  
OVERISEL TOWNSHIP - 170' SOUTH OF 143RD AVENUE  
**PLAN & PROFILE AND SOIL EROSION & SEDIMENTATION CONTROL PLAN**

DRAWN BY: RPB  
REVIEWED BY: JSE  
DATE: JANUARY, 2019  
SCALE: 1" = 40'H, 5'V


















**SOIL EROSION & SEDIMENTATION CONTROL NOTES**


- ALL CONSTRUCTION METHODS SHALL BE DONE IN COMPLIANCE WITH THE MICHIGAN SOIL EROSION AND SEDIMENTATION CONTROL ACT. THE OWNER SHALL BE RESPONSIBLE FOR OBTAINING A "SOIL EROSION PERMIT" FROM THE COUNTY AND A "PERMIT BY RULE/NOTICE OF COVERAGE" FROM THE MDEQ PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH ALL REQUIREMENTS OF THE COUNTY "SOIL EROSION PERMIT" AND FOR ALL CERTIFIED STORM WATER INSPECTION SERVICE REQUIRED BY THE "PERMIT BY RULE" EROSION CONTROL MEASURES SHOWN ON THE PLANS ARE THE MINIMUM REQUIREMENTS AND SHALL NOT RELIEVE THE CONTRACTOR'S RESPONSIBILITY FOR PROVIDING ALL REQUIRED EROSION CONTROL MEASURES.
  - AVOID UNNECESSARY DISTURBING OR REMOVING OF EXISTING VEGETATED TOPSOIL OR EARTH COVER, THESE COVER AREAS ACT AS SEDIMENT FILTERS.
  - ALL TEMPORARY SOIL EROSION PROTECTION SHALL REMAIN IN PLACE UNTIL REMOVAL IS REQUIRED FOR FINAL CLEAN UP AND APPROVAL.
  - GEOTEXTILE SILT FENCE SHALL BE INSTALLED AS REQUIRED WHEN CROSSING CREEKS OR WHEN ADJACENT TO WETLANDS OR SURFACE WATER BODIES TO PREVENT SILTATION AND ELSEWHERE AS DIRECTED BY THE ENGINEER. SEEDING AND/OR SODDING SHALL BE INSTALLED ON CREEK BANKS IMMEDIATELY AFTER CONSTRUCTION TO PREVENT EROSION.
  - MAINTENANCE, CLEANING, AND REMOVAL OF THE VARIOUS SEDIMENT CONTROL MEASURES SHALL BE INCLUDED IN THE VARIOUS EROSION CONTROL ITEMS.
- 3P ALL DISTURBED AREAS NOT PAVED OR GRAVELED SHALL BE RESTORED UNDER THE PAY ITEM RESTORATION (LUMP SUM). THIS PAY ITEM INCLUDES PLACING MDT SEEDING, MIXTURE T/F APPLIED AT A RATE OF 220 LB/ACRE, FERTILIZER, CHEMICAL NUTRIENT, CL APPLIED AT A RATE OF 176 LB/ACRE; MULCH AT A RATE OF 2 TON/ACRE AND MULCH ANCHORING.
- 3T TEMPORARY SEEDING WILL BE PLACED AT LOCATIONS DETERMINED BY THE ENGINEER IN THE FIELD AND WILL INCLUDE SEEDING MIXTURE, OR APPLIED AT A RATE OF 70 LB/ACRE AND MULCH.
- 4T DUST CONTROL MAY BE REQUIRED ON THE SUBGRADE CONSTRUCTION AND WILL INCLUDE APPLYING FRESH WATER TO BE INCLUDED IN THE ITEM OF EMBANKMENT. DUST CONTROL ON THE AGGREGATE BASE COURSE WILL BE ACCOMPLISHED BY APPLYING FRESH WATER (INCLUDED IN THE ITEM OF AGGREGATE BASE, 6 INCH) AS DIRECTED BY THE PROJECT ENGINEER.
- 7P INSTALL RIPRAP, HEAVY AS DIRECTED BY THE ENGINEER IN THE FIELD. THE RIPRAP, HEAVY PAY ITEM WILL INCLUDE A GEOTEXTILE UNDERLAYMENT.
- 26T SILT FENCE WILL BE INSTALLED AT CREEK CROSSINGS, ADJACENT TO ALL WETLANDS AND SURFACE WATERS, AND OTHER LOCATIONS AS DIRECTED BY THE ENGINEER. EACH SILT FENCE WILL BE INSTALLED GENERALLY ALONG THE SAME CONTOUR ELEVATION.
- 3S HIGH VELOCITY MULCH BLANKETS WILL BE USED ON STEEP BANKS. PROVIDE MULCH BLANKET, HIGH VELOCITY CENTERED ON ALL DITCH BOTTOMS WITH A LONGITUDINAL GRADE OF 2.00% OR GREATER AND AT OTHER LOCATIONS AS DIRECTED BY THE ENGINEER IN THE FIELD.

**STAGING NOTES**

- INSTALL TEMPORARY EROSION CONTROL MEASURES.
- CONSTRUCT THE TEMPORARY CHANNEL WITH A 6A STONE PILE AT EACH END AS A PLUG. AFTER LINING THE CHANNEL WITH GEOTEXTILE, OPEN THE DOWNSTREAM PLUG, ALLOW THE WATER TO EQUALIZE, AND THEN REMOVE THE UPSTREAM PLUG.
- REMOVE THE EXISTING 9' X 7' CMP CULVERT.
- INSTALL THE 16' X 8' PRECAST CONCRETE BOX CULVERT.
- OPEN THE CHANNEL FROM THE DOWN STREAM END AND ALLOW THE WATER TO EQUALIZE. OPEN THE UPSTREAM SIDE OF THE NEW CHANNEL AND PLUG THE TEMPORARY CHANNEL.
- BACKFILL THE TEMPORARY CHANNEL AND PRECAST CONCRETE BOX.
- INSTALL PERMANENT SOIL EROSION CONTROL MEASURES.



LEGEND					
SIGN NO.	QTY.	SIGN DESIGNATION	DESCRIPTION	SIZE	AREA
①	2 EA	W20-1		48 INCH x 48 INCH	32 SFT
②	3 EA	W20-3		48 INCH x 48 INCH	32 SFT
		D3-2a		36 INCH x 12 INCH	6 SFT
③	3 EA	W20-2		48 INCH x 48 INCH	32 SFT
④	4 EA	M4-9		30 INCH x 24 INCH	15 SFT
		D3-2a		36 INCH x 12 INCH	9 SFT
⑤	4 EA	M4-9		30 INCH x 24 INCH	15 SFT
		D3-2a		36 INCH x 12 INCH	9 SFT
⑥	2 EA	D3-2a		36 INCH x 12 INCH	6 SFT
		M4-8a		24 INCH x 18 INCH	6 SFT
⑦	2 EA	R5-18c		48 INCH x 48 INCH	32 SFT
⑧	2 EA	BARRICADE, TYPE III, HIGH INTENSITY, LIGHTED, 2 REQUIRED EACH LOCATION		2 REQUIRED EACH LOCATION	4 EA
		R11-4		60 INCH x 30 INCH	25 SFT
⑨	2 EA	G20-2		48 INCH x 24 INCH	16 SFT
				TOTAL AREA =	235 SFT



A PORTION OF OVERISEL TOWNSHIP  
 ALLEGAN COUNTY, MI  
 NOT TO SCALE

**Board of County Road Commissioners  
 Of Allegan County**  
 1308 LINCOLN ROAD  
 ALLEGAN, MICHIGAN 49010-9762  
 TELEPHONE (269) 673-2184 www.alleganroads.org FAX (269) 673-5922

REVISIONS
1
2
3
4
5
6
7

**46TH STREET CULVERT REPLACEMENT**  
 OVERISEL TOWNSHIP - 170' SOUTH OF 143RD AVENUE  
 DETOUR ROUTE

DRAWN BY: RPB  
 REVIEWED BY: JSE  
 DATE: JANUARY 2019  
 SCALE: NONE